



Sarawak Land Consolidation And Rehabilitation Authority
(SALCRA)

- SITE INSPECTION CERTIFICATE -

To: General Manager
SALCRA
Wisma SALCRA
Kota Samarahan

Dear Sir,

I. I hereby certify that the tenderer _____
(Name of Firm/Company)
has inspected the work site(s) _____
(Where the works are to be carried out),
today the _____ (date) and has fully satisfied himself with all
the conditions, nature of difficulties, nature of works and any other requirement to
be carried out in compliance with the Terms and Conditions of the Contract.

Date: _____
(Officer in-charge Rimbas OPE /Authorised Signatory)

II. I hereby declare that I, _____, I/C No. _____
(Name)

of _____ has today _____ (date)
(Name of the Company/Firm)
inspected the works site(s) where the works are to be carried out and has fully
satisfied myself with all the conditions, nature of difficulties, nature of works and
any other requirement to be carried out in compliance with the Terms and
Conditions of the Contract.

(Tenderer's Signature and Stamp)

Name: _____

Designation: _____

Witnessed By : _____
Name : _____
I/C No. : _____
Address : _____



SCOPE OF WORKS

1.0 Introduction

This tender is for **The Proposed Construction of Concrete Road Pavement at Rimbas Oil Palm Estates (Phase 12), Saratok Region.**

2.0 Scope Of Works for Concrete Road

(To be read in Conjunction with Schedule of Prices and Drawings)

This contract comprises of the following major works:-

- 2.1 Upgrading and concreting works with concrete Grade 25 of 20,500 Lin M of subsidiary road.
- 2.2 Mobilize to site necessary machinery, plants, equipment, tools, instruments, operators, workers, etc.
- 2.3 Setting out, peg road alignment.
- 2.4 Scarify and upgrade to chamber and compact the roadway including shoulder and roadside drain to smooth longitudinal grade, chamber and cross-falls. The cross falls of the carriageway shall be about 1:20 depending on the site conditions, i.e. gentler chamber for steep areas and more pronounced on flat area, compact and to form the side drains. Patches of soft soil shall be excavated, removed and substitute with good granular soil and consolidated. Soil used must consist of equal mixture of coarse and fine granular and agreed by the Superintending Officer or his Site Representative.
- 2.5 Supply, lay, spread and compact lower road-base materials 38mm diameter DCR to the required road level, width and length as per specification and drawings.
- 2.6 Supply, lay, spread and compact 150 mm thick of concrete Grade 25, width and length as per specification and drawings.
- 2.7 Top-up to required level the existing road shoulder with topsoil and maintain the existing roadside drain.
- 2.8 All other works, which are not specifically stated but deemed necessary for completion of the Works.
- 2.9 Site clearance of all temporary works and rubbish, demobilize upon certified practical completion.
- 2.10 To carry out maintenance within the **twelve (12) months** Defect Liability Period commencing after the certified practical date of completion.