



Sarawak Land Consolidation And Rehabilitation Authority
(Lembaga Penyatuan Dan Pemulihan Tanah Sarawak)
- SITE INSPECTION CERTIFICATE -

To: General Manager
SALCRA
Wisma SALCRA
Kota Samarahan

Dear Sir,

I. I hereby certify that the tenderer _____
(Name of Firm/Company)
has inspected the work site(s) _____
(Where the works are to be carried out),
today the _____ (date) and has fully satisfied himself with all
the conditions, nature of difficulties, nature of works and any other requirement to
be carried out in compliance with the Terms and Conditions of the Contract.

Date: _____
(Estate Manager Pakit OPE /Authorised Signatory)

II. I hereby declare that I, _____, I/C No. _____
(Name)
of _____ has today _____ (date)
(Name of the Company/Firm)
inspected the works site(s) where the works are to be carried out and has fully
satisfied myself with all the conditions, nature of difficulties, nature of works and
any other requirement to be carried out in compliance with the Terms and
Conditions of the Contract.

(Tenderer's Signature and Stamp)

Name: _____

Designation: _____

Witnessed By : _____
Name : _____
I/C No. : _____
Address : _____

SARAWAK LAND CONSOLIDATION AND REHABILITATION AUTHORITY

**THE PROPOSED CONSTRUCTION AND COMPLETION OF ONE (1) BLOCK
BLOCK OF 6 DOORS SEMI PERMANENT LABOUR BARRACK AT
PAKIT OIL PALM ESTATE, SRI AMAN**

SCOPE OF WORKS

NOS.	BRIEF DESCRIPTIONS OF WORKS/ITEMS
1	Mobilize to site necessary plant, equipment, tools, workers, labourers; expenses to obtain Performance Bond and Insurance, Stamping of Agreement fee, Temporary Workers' Accommodation, power supply; setting out and pegging; Site Clearing of temporary works and structures; making good of any defects to adjoining structures or services and demobilize upon certified practical completion.
2	To carry out necessary earthwork, site clearing, grubbing, survey and setting out and construction of building platform and external works.
3	To construct and complete one (1) block of 6 doors Semi Permanent Labour Barrack including perimeter drain, painting, internal plumbing and fittings, sanitary finishes and fittings, septic tanks, manholes and sewerage pipes. etc. as specified in the drawing.
4	To construct and complete 1.5m wide r.c walkway, r.c drain and steel cloth hanger as specified in the drawing.
5	Supply, install and complete water supply system including HDPE water main and 400-gallons water tank with platform, service line, connect to the existing main and to arrange with the Water Board for the water meter connection. testing and commissioning of the system.
6	Supply and install electrical wiring complete and all necessary accessories and fittings and to arrange with SESCO for the SESCO meter connection and testing and commissioning of the whole electrical system.
7	To liaise, arrange and seek approval from SESCO on the L.V External Overhead Distribution Cable, Terminal Boxes, Neutral Earthing, Service Lines, etc and all necessary for the satisfactory and commissioning complete of the external electrical installation.
8	To hand over in good condition the whole works to SALCRA upon certified practical completion by the Engineer-In-Charge.
9	All other works and items not stated above but deemed necessary for the satisfactory completion of the project.