

**SARAWAK LAND CONSOLIDATION AND REHABILITATION AUTHORITY
SCOPE OF WORKS**

No	Brief Description of works
1	Preliminary and general
2	Site clearing and grubbing of all trees, bushes etc. including demolish existing store, survey and setting out; construction of platforms to include earth cutting, excavation, backfilling and leveling to form suitable site level, drainage (Total Area to be cleared = 1650 m ²)
3	Construct and complete one (1) block of 6 doors semi permanent labour barrack including perimeter drain, painting, internal plumbing and fittings, sanitary finishes and fittings, polysept septic tank, manholes and sewerage pipes etc.
4	Supply, install and complete one (1) set of solar photovoltaics system including Internal Wirings & Fittings
5	Supply and install ten (10) units of rainwater harvesting 400-gallon polyethylene water tank blue in colour with platform and gutter inclusive all necessary piping, fitting and connection.
6	To construct and complete 230mm wide R.C perimeter drain 450mm (Approximate length = 27m)