

## **SARAWAK LAND CONSOLIDATION AND REHABILITATION AUTHORITY**

### **SCOPE OF WORKS**

<b>No</b>	<b>Brief Description of works</b>
1.	Preliminary and general.
2.	Site Preparation (e.g Site clearing, cut down and grubbing trees, bushes etc; Survey, setting out and leveling and demolition of the existing structures.
3.	Construct and complete of one (1) block of 4 doors permanent labour barrack including roofing, brick wall, perimeter drain, painting, doors and windows, kitchen sinks, tiling, internal plumbing and fittings, sanitary finishes and fittings, internal water storage tank, polysept septic tank, manholes and sewerage pipes, etc. as specified in the drawing.
4.	Water Supply installation including four (4) units of rainwater harvesting 400-gallon polyethylene water tank
5.	Internal Wirings & Fittings
6.	Construction of R.C Drain
7.	Construction of R.C Pathway